

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Kansas Nebraska Natural Gas Co., Inc

Complete Address Box 608, Hastings, Nebraska 68901

Lease Name Krioto Well No. 1

Location SE SE NW Sec. 35 Twp. 24 Rge. 35 ~~(E)~~ (W)

County Koarny Total Depth 2700'

Abandoned Oil Well        Gas Well        X Input Well        SWD Well        D & A        X

Other well as hereafter indicated None

Plugging Contractor Sargonts Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 30 Month 10 Year 1970

The above well was plugged as follows:

10 3/4" to 498' circulated w/ cement. ~~10~~ 7" to 2474' circulated w/ cement.

5 1/2" liner 2468' to 2700' No Perforations

Plug bottom w/ 120 sacks cement Top of cement 2204'

Mud 2204' to 550' Spotted 30 sacks cement 550' to 400'

Mud 400' to 50' Plug, Hulls & 10 sacks cement 50' to 0'.

Company Pump        No pipe Pulled.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Eves  
Well Plugging Supervisor

INVOICED

DATE 11/4/70

INV. NO. 2803-W