

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20201-00-02
Spot: NWSE Sec/Twnshp/Rge: 11-16S-43W
1960 feet from S Section Line, 1972 feet from E Section Line
Lease Name: EVANS E Well #: 2
County: GREELEY Total Vertical Depth: 5264 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5264	0	WITH 250 SX CMT
SURF	8.625	565		WITH 400 SX CMT

Well Type: EOR UIC Docket No: E26799.2 Date/Time to Plug: 07/12/2016 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS, LLC
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN LOEB Phone: (719) 340-8985

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2016 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****SLIDING SLEEVE AT 2965'. CEMENTED FROM 2965' TO 2520' PER BOND LOG. CEMENTED FROM 1890' TO 0' PER BOND LOG.** PUMP 50 SX CMT WITH 250# HULLS AT 5135' THROUGH TBG. PUMP 35 SX CMT WITH 100# HULLS AT 2809' INSIDE 5 1/2" CASING. FULL CIRCULATION. CIRCULATE CMT FROM 2006' TO SURFACE INSIDE 5 1/2" CASING WITH 210 SX CMT. TOOH WITH TBG. TOP OFF WITH 35 SX CMT. STAYED FULL. ATTEMPT TO PUMP CMT DOWN ANNULUS. COULD NOT AT 500#.**

Perfs:

Top	Bot	Thru	Comments
5160	5176		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
512 (TECHNICIAN)

RECEIVED
JUL 21 2016
KCC DODGE CITY *MD*

Form CP-2/3
AUG 18 2016
MD CC/CIC