

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-28392-00-01  
Spot: NESENE Sec/Twnshp/Rge: 22-23S-18E  
3400 feet from S Section Line, 495 feet from E Section Line  
Lease Name: DRAKE Well #: 8  
County: ALLEN Total Vertical Depth: 900 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 2.875 | 886        |             |         |
| SURF   | 6.5   | 20         |             |         |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/24/2009 12:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 10/24/2009 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe inside the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out. Hooked onto the 2.875" casing and pumped cement into the 2.875". Pressured well to 500 psi and shut in. A total of 65 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
AUG 09 2016  
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]  
(TECHNICIAN)

KCC WICHITA  
AUG 11 2016  
RECEIVED

8-11-16

Form CP-2/3  
Imaging Only  
AUG 17 2016  
[Signature]