

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-24270-00-00
Spot: NWSENE Sec/Twnshp/Rge: 22-23S-18E
3795 feet from S Section Line, 825 feet from E Section Line
Lease Name: DRAKE Well #: 1
County: ALLEN Total Vertical Depth: 1000 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	917		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2009 12:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: BERNIE RUCKERS Company: SPUTHRN STAR CENTRAL GAS PI Phone: (270) 852-5000

Proposed Plugging Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 09/30/2009 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out. Hooked onto the 2.875" casing and pumped cement into the 2.875". Pressured well to 600 psi and shut in. A total of 50 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
AUG 09 2016
CHANUTE, KS

RD

Remarks:
Plugged through: CSG

District: 03

KCC WICHITA
AUG 11 2016
RECEIVED

Signed [Signature] E. C. R. S.
(TECHNICIAN)

8-11-16

Form CP-2/3
Imaging only
AUG 17 2016
[Signature]