

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21175-00-00
Spot: NWSENWSW Sec/Twnslip/Rge: 21-17S-32W
1773 feet from S Section Line, 856 feet from W Section Line
Lease Name: EIKELBERGER Well #: 1-21
County: SCOTT Total Vertical Depth: 4775 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY SUITE 2
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	302		WITH 215 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/27/2016 5:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY STRUTT Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2360' WITH 50 SX CMT. 2ND PLUG AT 1570' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 07/27/2016 7:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 2360' WITH 50 SX CMT. 2ND PLUG AT 1570' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY.

Plugged through: DP

District: 01

Signed Gary Harris ECRS
(TECHNICIAN)

RECEIVED
AUG - 3 2016
KCC DODGE CITY

Form CP-2/3
AUG 1 8 2016

no