

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21081-00-00
Spot: NWSWNE Sec/Twshp/Rge: 28-27S-4E
3690 feet from S Section Line, 2340 feet from E Section Line
Lease Name: WILSON A Well #: 1
County: BUTLER Total Vertical Depth: 2450 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2092		
PROD	5.5	2450		75 SX
SURF	8.625	218		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2016 8:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: TE PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: AS PER KCC RULES & REGS / CEMENT BOTTOM BACK @ 2290', CIRC 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/29/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1984', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL 2% CC 40# HULLS & DISPLACED IN CASING. POOH W/TBG @ 255'. TAGGED CEMENT PLUG @ 1771'. RIH W/ 3/4" TBG ON BACKSIDE OF 5 1/2" CASING @ 255'. SWEDGED INTO 3/4" TBG, ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 70 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN 3/4" TBG. SWEDGED INTO TBG, ESTABLISHED CIRCULATION, CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TBG, TOPPED WELL BACK TO SURFACE W/10 SXS CEMENT. P&A COMPLETE 6/29/2016 5:00 PM. CONSOLIDATED CEMENT TICKET #51304. 130 SXS TOTAL ON TOP PLUG.

Perfs:

Top	Bot	Thru	Comments
2348	2352	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

Form CP-2/3

AUG 18 2016

no

DK