

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Hodgeman

County. Sec. 4 Twp. 24 Rge. 24 (E) (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE/NE/NE 1/4

Lease Owner Panhandle Eastern Pipe Line Co.

Lease Name Schneider Well No. 1

Office Address Box #979; Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 3 1951

Application for plugging filed October 2 1951

Application for plugging approved October 2 1951

Plugging commenced October 3 1951

Plugging completed October 3 1951

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Phillippe; Liberal, Kansas

Producing formation none Depth to top Bottom Total Depth of Well 4783 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Limestone	Sulphur Water	4706	4783	10-3/4	324	0
Conglomerate	Dry	4685	4706			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well drilled to 4783' with rotary tools. Hole was completely full of rotary mud.

Cement plug from 4658 to 4783'. (50 sacks in 9" hole)

Halliburton Cementing Co. used to introduce cement into drill pipe.

Rotary mud from 324 to 4658'.

Cement plug from 301 to 324.

Cement plug from 0 to 17.

324' of 10-3/4" surface pipe left in hole and a 1/4" steel plate welded on top of surface pipe which is 4' below ground level.

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1951

10-10-51

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Jack Phillippe

Address Box #979; Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.

Jack Phillippe (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack Phillippe

(Address)

SUBSCRIBED AND SWORN to before me this 9 day of October, 1951

Frederick J. Riley

Notary Public.

My commission expires 9/19/55

PLUGGING
FILE SEC 4 T 24 R 24
BOOK PAGE 114 LINE 2

28-5091-s

8-50-10M

LOG

Company: Panhandle Eastern Pipe Line Company
 Contractor: M. B. Armer (Unit rig)
 Drilling commenced: 9/9/51
 Drilling completed: 10/3/51

Farm: Schneider-#1-4
 Location: 4-24S-24W, - NE NENE,
 Hodgeman Co., Kansas
 Casing record: 10-3/4" set -
 at 324 ft.
 cemented w/200
 sacks.

(Figures below indicate bottom)

Shale and shells	105
Sand and shells	230
Blue shale	650
Sandy red bed	900
Red bed and shells	1110
Sand	1290
Shale and shells	1590
Anhydrite	1649
Shale and shells	2025
Shells and lime streaks	2095
Shale and salt	2335
Shale and lime	3285
Lime	3330
Blue and red shale	3410
Shale and lime	4195
Lime	4253
Shale and lime	4310
Lime	4365
Shale and lime	4425
Lime	4465
Shale and lime	4708
Lime	4783
Rotary Total Depth	4783 D & A

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By *M. B. Armer*

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a notary public, in and for said County and State this 9th day of October, 1951.

Walter
 Notary Public

My commission expires Sept. 17, 1955

PLUGGING
 FILE NO. 4783
 CHECK PAGE 14 LINE 7

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 13 1951
 CONSERVATION DIVISION
 Wichita, Kansas