


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 5 Twp. 24 Rge. 24 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Honaker-Davis Drlg. Co.
Lease Name Rogers Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-26 1957
Application for plugging filed 6-25 1957
Application for plugging approved 6-25 1957
Plugging commenced 10:00 P.M. 6-26 1957
Plugging completed 12:00 P.M. 6-26 1957
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	402	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 375'. Dumped in 1/3 sack hulls. Set plug with drill pipe. Mixed 20 sacks cement by hand and poured same through drill pipe.

Filled hole with heavy rotary mud to 35'. Dumped in 1/3 sack hulls. Set plug with Kelly. Mixed 10 sacks cement by hand. Filled surface pipe to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker-Davis Drlg. Co.
Address 2008 Lakin, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
S. C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of July, 1957.
Ruth O. Fisher
Notary Public.

My commission expires 6-25-59

7-8-57
-1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC 5 T 24 R 24W
BOOK PAGE 24 LINE 15

DRILLER'S LOG

Rogers No. 1
 Loc: SW SW SW
 Sec: 5-24-24
 Hodgeman County, Kansas
 Company: Honaker-Davis Drlg. Co., et al
 Contractor: Honaker-Davis Drlg. Co.


Comm: 6-9-57
 Comp: 6-26-57
 Rotary Total Depth: 4850'
 Casing: 8-5/8" at 402'
 D & A

0	40	Top soil & post rock	
40	250	Sand, Lime, Shale & post rock	
250	280	Shale & Lime	
280	340	Blue Shale & Lime Stone	
340	625	Blue Shale	8-5/8" casing cemented
625	830	Sand	at 402' with 275 sacks
830	1155	Red Bed & Shale	cement and 6 sacks
1155	1340	Sand	calcium chloride.
1340	1652	Red Bed & Shale	
1652	1677	Anhydrite	
1677	2060	Red Bed & Shale	
2060	2235	Shale & Shells	
2235	4115	Lime & Shale	
4115	4180	Lime	
4180	4545	Lime & Shale	
4545	4585	Lime & Chert	
4585	4685	Lime & Shale	
4685	4850	Lime & Chert	
4850		Total Rotary Depth	D & A

I certify that this is the true and correct copy of the
 above log to the best of my knowledge.


 H. S. Forbes

Subscribed and sworn to before me this 3rd day of July, 1957.


 Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

