


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Hodgeman County, Sec. 3 Twp. Rge. 24 (E) 24 (W)
Location as "NE/CNW/SW" or footage from lines CNE NE SW/4

Lease Owner M. B. Armer
Lease Name Schreader "B" Well No. 1
Office Address 710 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil - depleted
Date well completed Feb. 6, 1952
Application for plugging filed April 8, 1953
Application for plugging approved April 8, 1953
Plugging commenced April 9, 1953
Plugging completed April 14, 1953
Reason for abandonment of well or producing formation production depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production Feb. 13, 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Mississippian Depth to top 4674 Bottom 4718 Total Depth of Well 4718 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	202	None
				5 1/2"	4708	1677

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock 4718' to 4700'.
Dumped 5 sacks cement at 4700' with dump bailes,
top of cement 4665'. Filled hole with mud to 200',
set rock bridge, dumped 20 sacks cement. Top of
cement 160', filled with mud to 35', set rock bridge,
dumped 10 sacks cement for cap.

5-1-53
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor J & M Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 1953
Lorraine M. Johnson Notary Public.

My commission expires Oct. 13, 1956.

PLUGGING
FILE SEC 3 T 24 R 2 + W
BOOK PAGE 90 LINE 40

L O O

Company: M. B. Armer-Harry Koplin
 Contractor: M. B. Armer
 Drilling commenced: December 30, 1951
 Drilling completed: January 21, 1952
 Elevation: 2479 Gr. 2482 D. P. 2485 R. B.

Farat: Schrader - well #1 "B"
 Location: C. NE NE SW Sec. 3-24S-24W
 Hodgeman County, Kansas
 Casing records: 8-5/8" set @ 202' cemented
 with 175 sacks
 5 1/2" set @ 4708 cemented with
 200 sacks

(figures below indicate bottoms)

Surface Soil	20
Post rock & sand streaks	135
Blue shale & shells	190
Shale & shells	202
Blue shale, stricky & shells	670
Shale & shells	770
Redbed & shells	1100
Sand	1280
Shale & redbed & shells	1595
Anhydrite	1635
Shale & shells	2215
Shale & shells & salt	2420
Shale & shells	2560
Shale & lime	2910
Shale & shells & some anhydrite	3030
Shale & lime anhydrite streaks	3090
Shale & lime	3200
Shale & shells	3313
Shale & lime	3912
Chalky lime, red & blue shale	3937
Shale & lime	4667
Conglomerate	4674
Lime	4681
Shale & Lime	4708
Lime	4715
Rotary Total Depth	4715
Corrected to	4718

FORMATION TOPS: (R. D. Meas.)

Heebner	3966
Toronto	3985
1st Lans. Kansas City	4021
2nd Lans. Kansas City	4047
Basal Penn. Cong.	4667
Mississippian	4674

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

BY 

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 31st day of January, 1952.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 3 - 1953
 CONSERVATION DIVISION
 Wichita, Kansas

My commission expires Sept. 17, 1955.


 Notary Public
PLUGGING

FILE SEC 3 T 24 R 244
 BOOK PAGE 90 LINT 40