

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-19314-0000

LEASE NAME Zenith Unit

WELL NUMBER 11

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

5150 Ft. from S Section L

4290 Ft. from E Section L

SEC. 11 TWP. 24 RGE. 11 XR) of (W)

LEASE OPERATOR Sterling Oil Company, Inc.

ADDRESS 112 S. Broadway, Sterling, Ks 67579

PHONE# (316) 278-3727 OPERATORS LICENSE NO. 30108

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed -

Plugging Commenced 9:15 AM

Plugging Completed 12:15 PM

The plugging proposal was approved on 11-10-92 (date)

by Duane Rankin (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation - Depth to Top 3700 Bottom 3750 T.D. 3750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 10 3/4 | 245 | 0 |
| | | | | 7 | 3734 | 2132 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from - feet to - feet each
Bottom plug: Sanded to 3630 & bailed 6 sx cement.

Top plug: Pumped 300 lbs Hulls, 10 sx Gel, 70 sx Cement, 10 sx Gel, 100 lbs Hulls, 150 sx Cement (60/40 with 6% Gel) Max pressure of 650 & shut in of 250 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. RECEIVED #136

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sterling Oil Company, Inc. NOV 12 1992

STATE OF Kansas COUNTY OF Barton, ss. GARY G. BURKE


Gary G. Burke

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein and the log of the above-described well as filed, and the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 10 day of November, 19 92



My Commission Expires: 4-30-96

Anna K. Burke
Notary Public

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-185-19314-0000

COMPANY Braden-Zenith, Inc.

SEC. 11 T. 24S R. 11W
 LOC. 500' E and 100' S of
 NW Corner

FARM Zenith Unit NO. 11

COUNTY Stafford

TOTAL DEPTH 3,750 ft.

COMM. July 28, 1973


COMP. August 7, 1973

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED

KANSAS



CASING

20 10-3/4" - 245 ft. w/ 250 sxs.

15 8

12 6

13 5

7" - 3,734 ft. w/ 100 sxs.
FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 1,812 K.B.

PRODUCTION

| | |
|------------------------|--------|
| Sand | 150' |
| Red Bed | 245' |
| Red Bed, Shale, Shells | 270' |
| Shale and Shells | 1,200' |
| Shale and Lime | 1,775' |
| Lime and Shale | 2,003' |
| Shale and Lime | 2,750' |
| Lime and Shale | 2,890' |
| Shale and Lime | 3,030' |
| Lime and Shale | 3,125' |
| Lime | 3,505' |
| Lime and Shale | 3,568' |
| Lime | 3,750' |
| Rotary Total Depth | 3,750' |

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Merle Britting
 Merle Britting

State of Kansas }
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 10th. day of August, 1973.

Elsie Willison
 Elsie Willison - Notary Public

