


15-051-~~02566~~
02566-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ellis County, Sec. 31 Twp. 12 Rge. 20 (E) (W)
Location as "NE/CNWSW" or footage from lines C W/2 NW SE
Lease Owner Murfin Drilling Company
Lease Name Huber B#1 Well No.
Office Address Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8/28/73 19
Plugging completed 8/28/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	119	none
				7"	3833	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

~~DWELXX~~

Squeezed well with 30 sacks cement, 24 sacks gel, 5 sacks hulls, released plug and ran 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1973
9-13-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1973

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


COPY

Company - DARBY PETRO. CORP.
Farm - Huber "B" No. 1.

SEC. 31 T. 12 R. 20 W
NW 1/2 NE SE

Total Depth. 3845'
Comm. 8-3-43 Comp. 8-23-43
Shot or Treated.
Contractor. R.C. Patton Drlg. Co.
Issued. 12-25-43

County. Ellis
KANSAS



CASING:
10" 119'
7" 3833'

Elevation.

Production. Pot. 810 B.

Figures Indicate Bottom of Formations.

shale & sand	119
shale & shells	945
sand, shale, shells	1370
shale & shells	1529
anhydrite	1581
shale	1635
shale & shells	1930
salt, shale, shells	2100
shale & lime	2490
lime	2530
shale & lime	3310
lime	3800
lime brkn	3823
lime	3845
Total Depth.	

Tops: Anhydrite	1529
Lansing	3441
Conglomerate	3796
Arbuckle	3829

3829
1649

2180

lgt sat. & por. 3554-58
por., no sat. 3616-21
lgt sat. & por. 3835-40

3441
2180

1261

150' OIH/30 min. 3838
2860' OIH/17 hrs (overnight)
Drilled deeper 3838-45 TD
good pay 3845
2950' OIH additional
4 hrs 3845
3250' OIH T.F.U.

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1973
CONSERVATION DIVISION
Wichita, Kansas