


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 4 Twp. 16 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines N/2 NW SE
Lease Owner The Duke Drilling Company
Lease Name Davidson Well No. 1
Office Address Box 823, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 19 19 62
Application for plugging filed 4-19 19 62
Application for plugging approved 4-19 19 62
Plugging commenced 4-19 19 62
Plugging completed 4-19 19 62
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3344 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>8 5/8"</u>	<u>254'</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 400'
Set 20 sacks cement through drill pipe;
Filled hole to 240' set plug 1/4 sack hulls and 20 sacks
cement through drill pipe;
Filled hole to 35' Set plug 1/4 sacks hulls & 10 sacks cement.
Plugged rat hole.

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1962
4-24-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.
Address Box 823, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.
Lewis O. Chubb (Employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lewis O. Chubb
Lewis O. Chubb
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of April, 19 62

My commission expires June 24, 1963
Clair E. Scimson Notary Public.

DRILLER'S WELL LOG

Date Commenced: April 11, 1962
Date Completed: April 19, 1962

Duke Drilling Company
DAVIDSON #1
N/2 NW SE
Section 4-16s-11w
Barton County, Kansas

0 - 45'	Clay-Post Rock
45 - 75'	Blue Shale
75 - 120'	Sand
120 - 225'	Shale
225 - 398'	Red Bed
398 - 415'	Sand
415 - 460'	Shale
460 - 711'	Red Bed
711 - 740'	Anhydrite
740 - 1350'	Shale-Shells-Salt
1350 - 1895'	Shale & Lime
1895 - 2270'	Lime - Shale
2270 - 2560'	Shale - Shells
2560 - 2785'	Lime & Shale
2785 - 2894'	Lime
2894 - 2898'	Shale HEEBNER
2898 - 2914'	Lime Shale
2914 - 2924'	Lime TORONTO
2924 - 2987'	Shale DOUGLAS
2987 - 3002'	Lime Shale BROWN LIME
3002 - 3285'	Lime LANSING
3285 - 3332'	CONGLOMERATE
3332 - 3344'	Dolomite ARBUCKLE
3344	R.T.D.

ELEVATION: 1866 K.B.

FORMATION DATA:
Heebner 2894
Brown Lime 2987
Lansing 3002
Conglomerate 3285
Arbuckle 3332
R.T.D. 3344

SURFACE CASING: Set 254'
of 8-5/8" @ 250' with 165
sacks cement


RECEIVED
STATE CORPORATION COMMISSION

APR 24 1962
CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss.

Lewis O. Chubb of lawful age being duly sworn on oath, states that the facts and figures herein contained are true and correct to the best of his knowledge.



Lewis O. Chubb

Subscribed and sworn to before me this 23rd day of April, 1962.



Clair E. Stimson-NOTARY PUBLIC

My Commission Expires: June 24, 1963.