


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 32 Twp. 30 Rge. 7 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines NE NW

Lease Owner Mack Oil Company

Lease Name Hostettler Well No. 1

Office Address Kingman, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 2-12-66 19

Plugging completed 2-16-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 4769 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None
				4-1/2"	4769'	4308'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole and set 3 sacks of cement on bottom with dump bailer. Pulled 4 1/2" casing, set rock bridge @ 250' and dumped 25 sacks of cement. Mudded hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
2-23-66
FEB 23 1966

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/producer) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1966

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

MACK OIL COMPANY
Duncan, Oklahoma

DRILLERS WELL LOG

#1 Hostetler

C NE NW - Section 32-30S-7W
Kingman County, Kansas
Elevation: 1624' Kelly Bushing
Initial Production: Oil
Contractor: Mack Oil Company

Commenced R. D.: 11-11-65
Completed R. D.: 11-28-65
Rotary Total Depth: 4768'

STRATA	DEPTH
Sand	0 - 100'
Red Rock	100 - 170
Red Rock & Shells	170 - 254
Sand & Shale	254 - 415
Red Bed & Shale	415 - 1025
Sand	1025 - 1080
Shale & Shells	1080 - 1280
Shale	1280 - 1337
Lime & Shale	1337 - 2485
Shale & Lime Streaks	2485 - 2785
Shale & Shells	2785 - 2990
Lime & Shale	2990 - 3285
Lime	3285 - 3400
Lime & Shale	3400 - 3530
Lime	3530 - 3617
Lime & Shale	3617 - 3890
Lime	3890 - 4096
Lime & Shale	4096 - 4198
Lime	4198 - 4315
Lime & Shale	4315 - 4383
Lime	4383 - 4403
Chert	4403 - 4412
Lime & Chert	4412 - 4447
Cherty Lime	4447 - 4523
Lime & Chert	4523 - 4548
Lime	4548 - 4756
Viola Lime	4756 - 4768'

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1966
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Robert L. Harris
Robert L. Harris

Signed and sworn to in my presence this 30th day of November, 1965, by Robert L. Harris, representative of Mack Oil Company.

Elizabeth F. Nice
Elizabeth F. Nice, Notary Public

My commission expires September 21, 1968