

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-095-19152-0000
Form CP-4

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

KINGMAN County. Sec. 33 Twp. 30S Rge. 7W (E) (W)
Location as "NE/CNW/SW" or footage from lines G NW SW
Lease Owner Sierra Petroleum Co., Inc.
Lease Name GREIGHTON Well No. 1
Office Address 1015 Wichita Plaza Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed August 5, 1964
Application for plugging filed August 5, 1964
Application for plugging approved August 5, 1964
Plugging commenced August 5, 1964
Plugging completed August 5, 1964
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Herman E. Justus, Nickerson, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4788 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surf. Clay, sand, redbed & shale.	Surface Casing	-0-	205'	8-5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED HOLE: Filled hole to 200'. Put in 1/2 sk. hulls, 10 gal. crushed rock & 25 sx. cement. Filled hole to 46'. Put in 1/2 sk. hulls, plug & 9 sx. cement. Job completed at 7 p.m. Tore down.

RECEIVED
STATE CORPORATION COMMISSION
8-11-64
AUG 11 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 1015 Wichita Plaza Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
S. P. Hall, Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall, Superintendent

Box 232, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1964

My commission expires 10-17-67

Notary Public.

15-095-19152-0000

SIERRA PETROLEUM CO., INC. - Operator

T. D.: 4788'
Elev.: 1626' R.B.

CREIGHTON #1
C NW SW
Sec. 33-30S-7W
Kingman County, Kansas

Commenced: 7-23-64
Completed: 8-5-64

Casing:

8-5/8" Set at 205'

Cement:

with 190 sx. GL-3

FORMATION

DEPTH

Surface Clay	15
Sand	90
Redbed & Shale w/ Shells	175
Redbed & Shale	1150
Shale & Shells w/ Salt Streaks	1270
Shale & Anhydrite Shells	1500
Lime & Shale	3815
Lime	4382
Lime & Chert	4389
Lime	4410
Lime & Chert	4475
Lime	4665
Shale & Lime	4732
Lime	4785
Sand	4788

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1964

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF RUSSELL) ss:

I hereby certify that the above information is true and
correct to the best of my knowledge.

S. B. Hall
Superintendent

Subscribed and sworn to before me this 10th day of August,
1964.

Leroy Ditz
Notary Public

My commission expires: 10-17-67