

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas, 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 36 TWP. 30 RGE. 7W E/W
Location as in quarters or footage from lines:
C NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Rains & Williamson Oil Co., Inc.
Lease Name Russell B #1 Well No. _____
Office Address 435 Page Court Bldg. 220 W. Douglas Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6-16-83
Plugging completed 6-21-83
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ bottom T.D. 4722 1/2'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	227'	none
				5-1/2"	4720 1/2'	2696'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped bottom with 40 sacks cement, 6 sacks gel and 1 sack hulls. Shot casing
@3193', 3036', 2907', 2813' and 2701' and pulled a total of 84 joints (2696')
of 5-1/2" casing. Plugged well with 3 hulls, 6 gel, 8-5/8" plug and 100 sacks
cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd. day of June 1983

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

JUN 24 1983

CONSERVATION DIVISION
Wichita, Kansas

6-24-83

OPERATOR: Rains & Williamson Oil Co.
 #1 Russell "B"
 C NW SE Sec. 36-30S-7W
 Kingman County, Kansas

Commenced: 11/26/65
 Completed: 12/10/65
 Remarks: Set 227' 8-5/8" surface casing w 180 sx cement.

Set 5 1/4" casing 2' off bottom @ 4720 1/2'. Cemented w 125 sx salt saturated cement.

FORMATIONS

Sand	125'
Shale & Red Bed	1202'
Anhydrite	1235'
Lime & Shale	1655'
Lime	1830'
Lime - Shale	1859'
Lime & Shale	2035'
Shale & Lime	3400'
Lime - Shale	3605'
Sand - Lime	3650'
Lime	4340'
Lime & Shale	4346'
Cherty Lime	4365'
Lime - Chert	4380'
Lime & Chert	4590'
Shale	4597'
Shale & Lime	4722 1/2'
Rotary Total Depth	4722 1/2'

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 14th day of December, 1965.

My Commission Expires:
 July 25, 1968

Judith Caughlin
 Judith Caughlin, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

MAY 02 1983

CONSERVATION DIVISION
 Wichita, Kansas