

15-095-21121-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 36 TWP. 30s RGE. 7W E/W
Location as in quarters or footage from lines:

660' FEL & 1980' FNL

Lease Owner Coastal Oil & Gas

Lease Name Durant #4 Well No. _____

Office Address Box 889 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 12-17-81

Plugging completed 12-28-81

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom T.D. 4900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	335'	none
				5-1/2"	4898'	2451'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Shot pipe @3410' and 3120'. Pushed plug to 3060', sanded back to 3000' and ran 5 sacks cement. Shot pipe @2840', 2760', 2680', 2600', 2520' and 2420'. Pulled a total of 61 joints of pipe. Plugged well with 15 sacks gel, 6 sacks hulls, 10 sacks gel, released plug and displaced with 150 sacks common cement, 2% gel, 3% cc. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casign Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 82

My Commission expires:



Irene Hoover
Notary Public.

JAN 14 1982 1-14-82

CONSERVATION DIVISION
Wichita, Kansas