

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,783-0000

LEASE NAME Homo[ka]

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3960 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 1 TWP. 16 RGE. 11 (X) or (W)

COUNTY Barton

LEASE OPERATOR Cougar Drilling Co., Inc.

ADDRESS 555 N. Woodlawn, Suite 114, Wichita, KS 67208

PHONE (316) 685-7677 OPERATORS LICENSE NO. 5138

Date Well Completed 11-16-84

Character of Well D & A

Plugging Commenced 11-16-84

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-16-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office, Hays, KS

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION
12-14-84
DEC 14 1984

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

D&A - Plugged as follows: Filled hole w/mud, spot 90 sx 50/50 Pozmix, 6% gel, 3% cc, 2# cello flake per sk thru open end drill pipe @ 650', mud to 400', spot 40 sx cement thru open end drill pipe, mud to 40', 1/2 sk hulls & wooden plug for solid bridge, pumped 10 sx to base of cellar, circulated 10 sx in rathole. Completed @ 5:15 PM 11-16-84 by Allied.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cougar Drilling Co., Inc. License No. 5138

Address 555 N. Woodlawn, Suite 114, Wichita, KS 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.


John S. Crowe

~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~ or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 555 N. Woodlawn, #114, Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1984



[Signature]
Notary Public



555 N. Woodlawn
Suite 114
Wichita, Kansas 67208
Phone 316 - 685-7677

WELL LOG

OPERATOR: Cougar Drilling Co., Inc.
555 N. Woodlawn, Suite 114
Wichita, KS 67208

LEASE: Homolka #1

LOCATION: 3960' FSL & 4290' FEL of Section 1-16-11W, Barton County, Kansas

COMMENCED: November 12, 1984
COMPLETED: November 16, 1984

Rotary Total Depth: 3360' KB

FORMATION DESCRIPTION	TOP	BOTTOM
Soil, Post Rock	0	40
Shale	40	295
Dakota Sand	295	395
Red Beds	395	435
Red Beds, Shale	435	1685
Shale, Lime	1685	3035
Kansas City	3035	3315
Conglomerate	3315	3360 RTD

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1984

CONSERVATION DIVISION
Wichita, Kansas