

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

15-009-21252-000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 5 Twp. 16S Rge. 11W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

W/2 - NE NE
Lease Owner Hummon Oil Corporation
Lease Name Foster Well No. 1
Office Address 400 One Main Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Oil



Locate well correctly on above Section Plat

Date Well completed 10-14 1977
Application for plugging filed 3-4- 1981
Application for plugging approved 3-5- 1981
Plugging commenced 4-6- 1981
Plugging completed 4-17 - 11:15 1981
Reason for abandonment of well or producing formation Not Productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3280
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	275	None
				5 1/2	3275	2075

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand - Cover perforation
Sand from 3280 to 2920
5 sacks cement 2920 to 2885
Pulled 2074 feet 5 1/2"

Pumped in 300 lbs. hulls - 17 sacks Jell - 100 lb. Hulls
25 sacks cement - 3 sacks Jell - 100 lbs. Hulls.
Released plug pump in 100 sacks cement - 50-50 POZ - 4% Jell 3% C.C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation 583

STATE OF Kansas COUNTY OF Barber, ss.
Elma R. Margenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elma R. Margenstern
Medicine Lodge, KS.
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of April, 19 81

Jessie Hamilton
Notary Public.

My commission expires April 4, 1982

DRILLER'S WELL LOG

15009-21252-0000

DATE COMMENCED: 10-8-77
DATE COMPLETED: 10-14-77

Hummon Oil Company
Foster #1
W/2 NE NE Sec. 5-16S-11W
Barton County, Kansas

ELEVATION: 1801 K.B.
1799 D.F.
1796 G.L.

FORMATION DATA Log Tops

0- 657' Shale - Sands
657- 687' Anhydrite
687-2834' Shale and Lime
2834-2839' Shale
2839-2927' Lime and Shale
2927-2942' Lime and Shale
2942-3211' Lime
3211-3271' Lime and Shale
3271-3280' Dolomite
3280' RTD

Anhydrite	657	+1144
Heebner	2834	-1033
Brown Lime	2927	-1126
Lansing	2942	-1141
Base Kansas City	3211	-1410
Arbuckle	3271	-1470
RTD	3280	-1479

SURFACE PIPE:

Set 275' of 8 5/8" 28# w/175 sks.
common, 2% Gel, 3% c.c.
By Allied
Cement did circulate.

PRODUCTION PIPE:

Ran 102 Jts. Used 5 1/2" 14# Casing.
Set @ 3275' w/100 sks. Pozmix,
18% salt saturated. By Halliburton.
P.D. @2:00 p.m.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

DALE L. SMITH, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Dale L. Smith

Subscribed and sworn to before me this 17th day of October 1977.

Wanda Nichols
Notary Public

My commission Expires: 1-28-1980

