

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23918-00-00  
Spot: NENWSWSW Sec/Twnshp/Rge: 2-10S-20W  
1008 feet from S Section Line, 410 feet from W Section Line  
Lease Name: NUTSCH A Well #: 1  
County: ROOKS Total Vertical Depth: 3907 feet

Operator License No.: 32278

Op Name: TENGASCO, INC.

Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3904		150 SX
SURF	8.625	265		175 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/10/2016 8:00 AM

Plug Co. License No.: 32332

Plug Co. Name: FISCHER WELL SERVICE, INC.

Proposal Rcvd. from: GARY WAGNER

Company: TENGASCO INC.

Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.  
Port Collar at 1744' w/230 sx cement.  
Production perforations: 3816' - 3830'.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/10/2016 11:00 AM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Used sure shot to try to shoot tubing off at 3710'. Tubing backed off at 3400'. Still stuck in hole at 3400'. Hooked to tubing and pumped 250 sx cement to circulate to surface. Pulling unit crew backed tubing off at 3400'. Pulled tubing. Hooked to 5 1/2" casing and pumped 50 sx cement. Shut in pressure 450 psi.  
Hooked to 8 5/8" x 5 1/2" annulus and pumped 1/4 bbl. Shut in pressure 300 psi.  
Left 14 joints of tubing and tubing anchor in the hole.

Top	Bot	Thru	Comments
3816	3830		

GPS: 39.20797N -099.52950W

Remarks: QUALITY OILWELL CEMENTING TICKET # 1543

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

JUN 29 2016

JUL 08 2016

CONSERVATION DIVISION  
WICHITA, KS

JUN 29 2016

Form CP-2/3