

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26143-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 7-17S-13W
2202 feet from S Section Line, 2148 feet from E Section Line
Lease Name: TRENSE Well #: 1-7
County: BARTON Total Vertical Depth: 3560 feet

Operator License No.: 35130
Op Name: TYLUKA OPERATIONS, LLC
Address: 2308 PLUM ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	954		350 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/08/2016 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 235 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY WitnessType: NONE
Date/Time Plugging Completed: 06/09/2016 5:30 PM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

Perfs:

1st plug @3439 w/50 sx
2nd plug @1000 w/50 sx
3rd plug @500 w/80 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Chris Neeley

(TECHNICIAN) NO CM

JUN 24 2016

Received
KANSAS CORPORATION COMMISSION

JUL 08 2016

CONSERVATION DIVISION
WICHITA, KS

JUL 29 2016

Form CP-2/3