

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23327-00-00
Spot: NWSEWSW Sec/Twnshp/Rge: 19-9S-20W
1935 feet from S Section Line, 805 feet from W Section Line
Lease Name: COPELAND Well #: 1
County: ROOKS Total Vertical Depth: 3890 feet

Operator License No.: 34559
Op Name: WM KS ENERGY RESOURCES LLC
Address: 1001 FANNIN, STE 4000
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3887		175 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/05/2016 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: BRETT HILDEBRAND Company: WMKS ENERGY RESOURCES Phone: (785) 871-7311

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 16 sx gel and 500 # hulls.
1775' to surface with 300 sx cement.
Production perforations: 3811' - 3814'.
Casing leak : 1430' - 1461'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/05/2016 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3737' and pumped 16 sx gel followed by 50 sx cement w/250 # hulls. Pulled tubing to 1810' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 894' and pumped 100 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing with 10 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Shut in pressure 300 psi.

GPS: 39.25451N -099.60252W

Perfs:

Top	Bot	Thru	Comments
3812	3814		
3811	3814		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1724

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

JUL 06 2016

Received
KANSAS CORPORATION COMMISSION

JUL 08 2016

CONSERVATION DIVISION
WICHITA, KS

7-8-16

MO
JUL 29 2016 Form CP-2/3