

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-113-04658-00-00  
Spot: SENWSWSE Sec/Twnshp/Rge: 4-21S-3W  
966 feet from S Section Line, 2268 feet from E Section Line  
Lease Name: KREHBIEL Well #: 6  
County: MCPHERSON Total Vertical Depth: 3421 feet

Operator License No.: 6523  
Op Name: SCHMIDT, KERMIT AND TRACY SCHM  
Address: 308 WESTLANE RD  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	1175		0 SX
SURF	13	250		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/12/2016 2:30 PM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: SET BRIDGE PLUG @ 3382". PERF @ 450' TOP TO 250'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/12/2016 2:30 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

SPOTTED 35 SX, 5% GEL WITH CALCIUM CHLORIDE AND 50 LBS OF COTTON SEED HULLS ON BOTTOM @ 3309'. PERF @ 450' AND SPOTTED 5 SX CMT, 5% GEL AND PRESSURED UP TO 100 PSI. PERF @ 250' AND SPOTTED 200 SX 5% GEL AND C/C. WAITED 2 HOURS PUMPED ANOTHER 100 SX BETWEEN THE 16" AND 7" CASING. TOPPED OFF THE 7" CASING WITH 10 SX.

Perfs:

Top	Bot	Thru	Comments
3255	3309		CSG
425	450		CSG

Remarks:

Plugged through: CSG

District: 02

Signed Jerry Sparling  
(TECHNICIAN)

*NO*  
*JUL 29 2016*

KCC WICHITA  
Form CP-2/3

JUL 19 2016

RECEIVED

*JK*