

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-055-22177-01-00
 Spot: S2S2SESW Sec/Twnshp/Rge: 13-23S-31W
182 feet from S Section Line, 3228 feet from E Section Line
 Lease Name: SONDEREGGER 2331 Well #: 1-13H
 County: FINNEY Total Vertical Depth: 4874 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5015		
COND	20	130		WITH 13 SX CMT
LI	4.5	9230		WITH 500 SX CMT
PROD	7	5333	1546	WITH 300 SX CMT
SURF	9.625	1798		WITH 615 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2016 1:00 PM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Tag existing CIBP @ 5015', circulate hole with mud & spot 50 sks cement to cap CIBP & cover liner top. NU BOP and weld on 7" pull sub. Cut & pull free production csg. Spot 100 sks cement @ 1848'. Spot 50 sks @ 1250'. Spot 50 sks cement @ 625'. Top out @ 64' w/30 sks cement. Cut & cap well. Dig up rig anchors.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 06/30/2016 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5015'. RUN TBG TO 5015' & SPOT 50 SX CMT TO COVER LINER TOP AT 4916'. CUT 7" CASING AT 1895'. LOST 349' OF 7" BACK DOWN THE WELL. TOP OF 7" FISH AT 1546'. RUN TBG TO 1984' & SPOT 100 SX CMT. FULL CIRCULATION. PULL TBG TO 1250' & LOAD HOLE WITH 2 BBLs. PLUG AT 1250' WITH 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 64' TO 4' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8450	8721		
8092	8346		
7702	7962		
7327	7582		
6947	7210		
6568	6824		
6140	6446		
5806	6065		
5438	5676		
5050	9077		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C COMMON CEMENT BY ORR ENTERPRISES. TMD = 9230'.

Plugged through: TBG

District: 01

RECEIVED
 JUL 11 2016
 KCC DODGE CITY

Signed

[Signature]
 (TECHNICIAN)

JUL 29 2016

[Signature]
 KMS