

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-20632-00-01
Spot: NENESW Sec/Twnshp/Rge: 27-8S-26W
2206 feet from S Section Line, 2739 feet from E Section Line
Lease Name: ROBBEN Well #: 10-27
County: SHERIDAN Total Vertical Depth: 4010 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3998		200 SX
SURF	8.625	190		170 SX

Well Type: EOR UIC Docket No: E22267.1 Date/Time to Plug: 07/05/2016 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PETER FIORINI Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
8 5/8" surface casing set at 190' w/170 sx cement.
4 1/2" production casing set at 3998' w/200 sx cement.
TD 4010', PBSD 3958'.
Perforations: 3868' - 3872'.
DV Tool set at 2187' w/400 sx cement.
Casing holes: 2175' - 2208'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/05/2016 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3800' and pumped 85 sx cement w/250 # hulls. Pulled tubing to 2600' and pumped 85 sx cement w/200 # hulls. Pulled tubing to 1300' and pumped 85 sx cement w/150 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 35 sx cement. Connected to 8 5/8" surface casing and pumped 10 sx cement. Pressured to 200 psi. Braden head ruptured.

GPS: 39.32654N -100.20917W

Perfs:

Top	Bot	Thru	Comments
3868	3872		

Remarks: GLOBAL CEMENTING TICKET # 2611

Plugged through: TBG

District: 04

Received
KANSAS CORPORATION COMMISSION

Signed

Darrel Dipman
(TECHNICIAN)

JUL 27 2016

CONSERVATION DIVISION
WICHITA, KS

7-27-16

JUL 29 2016

CC UIC

Form CP-2/3