

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23110-00-01  
Spot: NWSWSE Sec/Twnshp/Rge: 22-6S-20W  
990 feet from S Section Line, 2200 feet from E Section Line  
Lease Name: CHAPMAN Well #: 4  
County: ROOKS Total Vertical Depth: 3700 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3696		115 SX
SURF	8.625	246		180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/26/2016 1:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Port Collar at 1742' w/200 sx cement.  
Production perforations: 3533' - 3654'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/26/2016 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' and pumped 200 sx cement w/300 # hulls. Pulled tubing to 1600' and pumped 155 sx cement w/200 # hulls. Pulled all tubing. Hooked to 5 1/2" casing and pumped 15 sx cement w/300 # hulls. Hooked to 8 5/8" x 5 1/2' annulus. Pressured up with less than 3/4 bbl.

GPS: 39.51302N -099.53570W

Perfs:

Top	Bot	Thru	Comments
3533	3536		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1703

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

NO  
29 2016 CA

JUN 14 2016

JUL 08 2016

CONSERVATION DIVISION  
WICHITA, KS