

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20699-00-03
Spot: SESWNE Sec/Twnshp/Rge: 36-15S-18W
2310 feet from N Section Line, 1650 feet from E Section Line
Lease Name: WERTH Well #: 1
County: ELLIS Total Vertical Depth: 3455 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3406		
PROD	5.5	3452		130 SX
SURF	8.625	1053		475 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/19/2016 8:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. DBA Phone: (785) 216-0155

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Operator elected all cement plug.
Well is in Hays well head protected area.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2016 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

E L I perforated at 1040'. Ultimate Well Service ran in hole with tubing to 3301' and pumped 150 sx cement w/300 # hulls mixed in. Pulled tubing to 1850' and pumped 350 sx cement w/400 # hulls to circulate cement up 5 1/2" casing. Pulled tubing. Rigged to 5 1/2" casing and topped off with 25 sx cement. Rigged to 8 5/8" surface casing and pumped 75 sx cement to pressure. Blew a small hole in head. No shut in pressure.

GPS: 38.70498 -099.27044

Perfs:

Top	Bot	Thru	Comments
3452	3457		
3336	3338		
3314	3320		
3269	3272		
3223	3227		
3154	3157		
3081	3090		
3074	3078		
3065	3070		
2901	2910		

Remarks: GLOBAL CEMENTING

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

JUL 27 2016

CONSERVATION DIVISION
WICHITA, KS

JUL 28 2016

7-27-16

[Signature]
(TECHNICIAN)

JUL 29 2016

CM