

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20758-00-01
Spot: NWSENENE Sec/Twnshp/Rge: 32-1S-35W
4565 feet from S Section Line, 651 feet from E Section Line
Lease Name: CAHOJ Well #: 1
County: RAWLINS Total Vertical Depth: 4430 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3180		395 SX
SURF	8.6258	302		200 SX

Well Type: SWD UIC Docket No: D26219.0 Date/Time to Plug: 07/08/2016 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GLENN DINKEL Company: PALOMINO PETROLEUM Phone: (316) 799-1000

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
8 5/8" surface casing set at 302' w/200 sx cement.
4 1/2" production casing set at 3180' w/395 sx cement.
TD 4430. PBSD 3150'.
Perforations: 2954' - 3090'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2016 10:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 2886' and pumped 105 sx cement w/300 # hulls. Pulled tubing to 1543' and pumped 105 sx cement w/200 # hulls. Cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 30 sx cement. Excavated braden head. Visible cement in braden head outlets.

GPS: 39.92783N -101.26313W

Perfs:

Top	Bot	Thru	Comments
2954	3090		
2950	3038		

Remarks: CONSOLIDATED OILWELL SERVICES TICKET # 51,501

Plugged through: TBG

District: 04

Received
KANSAS CORPORATION COMMISSION

Signed

Darrel Dipman

(TECHNICIAN)

JUL 27 2016

CONSERVATION DIVISION
WICHITA, KS

no
JUL 29 2016
CC UIC
CP-2/3

JUL 11 2016