

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-10068-00-00
Spot: NE Sec/Twnshp/Rge: 21-32S-43W
4033 feet from S Section Line, 1327 feet from E Section Line
Lease Name: SAUNDERS Well #: 1-21
County: MORTON Total Vertical Depth: 3371 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3300
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3342	0	WITH 400 SX CMT
SURF	8.625	657		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/11/2016 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: BRAD KEMPKE Company: NADEL & GUSSMAN Phone: (620) 697-2137

Proposed Plugging Method: TOP OF FISH @2200'. PLUG AT 2200' WITH 25 SX CMT. PLUG AT 1400' WITH 25 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/12/2016 1:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

RTIH TO 2200'. 1ST PLUG AT 2200' WITH 25 SX CMT. 2ND PLUG AT 1400' WITH 25 SX CMT. SHOT CASING AT 717'. WASN'T FREE. SHOT CASING AT 588'. PULLED 10' & GOT STUCK AGAIN. RTIH TO 1100'. 7/12/12: TBG WON'T GO PAST 600'. PUMP 300# HULLS & MUD. LOAD CASING TO PUSH HULLS DOWN TO CASING. LEAK. 3RD PLUG AT 600' WITH 50 SX CMT. GOOD RETURNS. 4TH PLUG AT 90' TO 0' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3111	3138		
3076	3082		
3064	3070		
3048	3057		
3029	3035		
2938	2970		
2906	2910		
2895	2898		
2850	2858		
2825	2840		
2775	2784		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
JUL 21 2016
KCC DODGE CITY

JUL 29 2016 Form CP-2/3