

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21268-00-01
Spot: NESWSE Sec/Twnshp/Rge: 8-11S-31W
1017 feet from S Section Line, 1801 feet from E Section Line
Lease Name: WIELAND A Well #: 5
County: GOVE Total Vertical Depth: 4750 feet

Operator License No.: 3273 String Size Depth (ft) Pulled (ft) Comments
Op Name: HERMAN L. LOEB, LLC PROD 4.5 4734 150 SX
Address: PO BOX 838 SURF 8.625 235 165 SX
LAWRENCEVILLE, IL 62439

Well Type: EOR UIC Docket No: E27692.1 Date/Time to Plug: 06/22/2016 10:30 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN LOEB Phone: (719) 340-8985

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Second stage: 2478' w/1275 sx cement.
Perforations: 4210' - 4214', 4263' - 4269' and 4504' - 4507'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2016 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4116' and pumped 50 sx cement w/150 # hulls. Pulled tubing to 3616' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 2966' and pumped 75 sx cement. Pulled tubing to 1966' and pumped 75 sx cement. Pulled tubing to 966' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 5 sx cement. Tied on to backside and squeezed with 12 sx cement.

GPS: 39.10766 -100.78151

Perfs:


Top	Bot	Thru	Comments
4504	4507		
4263	4269		
4210	4214		

Remarks: ALLIED CEMENT TICKET # 68004

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUN 23 2016

JUL 08 2016

CONSERVATION DIVISION
WICHITA, KS

no
JUL 29 2016
cc UIC
Form CP-2/3