

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21865-00-00
Spot: N2NESESE Sec/Twnshp/Rge: 34-30S-12W
1004 feet from S Section Line, 347 feet from E Section Line
Lease Name: HAAS Well #: 6
County: BARBER Total Vertical Depth: 4281 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|--------|------------|-------------|-----------------|
| COND | 13.375 | 54 | | |
| PROD | 4.5 | 4278 | 2100 | WITH 200 SX CMT |
| SURF | 8.625 | 237 | | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2016 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Recvd. from: ALAN VRATIL Company: HERMAN LOEB Phone: (620) 886-2419

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS & 5 SX CMT. PLUG AT 740' WITH 12 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2016 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4070' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 740' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4206 | 4214 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JUL 08 2016
KCC DODGE CITY

NO
JUL 29 2016 Form CP-2/3

KMS