

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22408-00-00
Spot: S2SENE Sec/Twnshp/Rge: 21-32S-14W
2991 feet from S Section Line, 774 feet from E Section Line
Lease Name: JUDY HOAGLAND Well #: 3-21
County: BARBER Total Vertical Depth: 4766 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4560		WITH 2 SX CMT
COND	10.75	288		WITH 205 SX CMT
PROD	4.5	4760	2350	WITH 200 SX CMT
SURF	8.625	1310		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/01/2016 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN LOEB Phone: (620) 886-2419

Proposed Plugging Method: CIBP @ 4558' WITH 2 SX CMT. PLUG AT 1360' WITH 15 SX GEL & 50 SX CMT. PLUG AT 840' WITH 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/01/2016 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4560' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1360' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 840' WITH 50 SX CMT. 3RD PLUG AT 420' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4658	4668		
4608	4616		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed

Steve Pfeifer
(TECHNICIAN)

RECEIVED
JUL 08 2016
KCC DODGE CITY

JUL 29 2016 Form CP-2/3

KMS