

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-22108-00-00
Spot: W2E2NENE Sec/Twnshp/Rge: 15-28S-6W
660 feet from N Section Line, 530 feet from E Section Line
Lease Name: CLOUSE 'G' Well #: 4-15
County: KINGMAN Total Vertical Depth: 4230 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4198	2900	190 SX
SURF	8.625	252		190 SX
T1	2.375	3838		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/03/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 297-3222

Proposed Plugging Method: Per KCC recommendation

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/05/2015 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PUMPED 200# HULLS AND 30 SKS OF CEMENT TO 3200' AND SI WITH 800#. RECOVERED 2900' OF 5.5 CASING. PULLED CASING TO 850' AND PUMPED 35 SKS OF CEMENT. PULLED CASING TO 360' AND PUMPED 150 SKS OF CEMENT. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3872	3882		

Remarks: QWS COMMON CEMENT

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

no
JUL 29 2016

KCC WICHITA Form CP-2/3

JUL 19 2016

RECEIVED