

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-01271-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 28-19S-2W
2310 feet from N Section Line, 1980 feet from E Section Line
Lease Name: LIVELY Well #: 4
County: MCPHERSON Total Vertical Depth: 2969 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2925		75 SX
SURF	8.625	162		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2016 11:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: VAN C. BACON Company: LOEWEN OPERATORS Phone: (620) 628-4723

Proposed Plugging Method: 8.625" 162' TO SURFACE 125 SX. 5.5" 2958' TO SURFACE 75 SX.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 06/27/2016 11:00 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

6-23-2016 CEMENTED BOTTOM 5 SX 2969'. PUT 1' DOWN BACKSIDE SOLID AT 20 FEET. WELL HAD BEEN SQUEEZED PRIOR TO PLUGGING. PERFORATED AT 450' PUMPED 35 SX. PULLED UP 250' PUMPED 80 SX. STOPPED AFTER THE RIG LOST CIRCUALTION. 6-27-16 BAILED HOLE (DROPPED IN TO 500') TAGGED CEMENT PULLED APPROX. 20 GALLONS OF FLUID WITH BAILER. CEMENTED FROM 500' TO SURFACE 60 SX. 2% GEL AND 2 SX COTTONSEED HULLS.

Perfs:

Top	Bot	Thru	Comments
2930	2969		OH

Remarks: WELL HAD BEEN SQUEEZED AT AN EARLIER REPAIR

Plugged through: CSG

District: 02

Received
KANSAS CORPORATION COMMISSION
JUL 08 2016
CONSERVATION DIVISION
WICHITA, KS

Signed

Jerry Sparling
(TECHNICIAN)

JUL 29 2016