

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23809-00-00  
Spot: NWSESWNE Sec/Twnshp/Rge: 20-9S-21W  
2215 feet from N Section Line, 1915 feet from E Section Line  
Lease Name: KORTAN Well #: 1  
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 33937  
Op Name: NEAL LAFON REALTY INC. DBA MERI  
Address: 1475 WARD DR  
FRANKTOWN, CO 80116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3894		400 SX
SURF	8.625	211		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2016 8:30 AM  
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE, LLC  
Proposal Rcvd. from: BRETT HILDEBRAND Company: BLACK OPS WELL SERVICE Phone: (785) 871-7311

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/250 # hulls and 17 sx gel.  
Perforations: 3848' - 3852', 3858' - 3868'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2016 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3821' and pumped 17 sx gel followed by 50 sx cement w/250 # hulls. Pulled tubing to 1813' and pumped 100 sx cement. Pulled tubing to 907' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 200 psi.

GPS: 39.25729 -099.68665

Perfs:

Top	Bot	Thru	Comments
3848	3852		

Remarks: QUALITY CEMENT TICKET # 1725

Plugged through: TBG

District: 04

Signed

*Marvin Mills*

(TECHNICIAN)

*MD*  
JUL 29 2016  
CM

Received  
KANSAS CORPORATION COMMISSION

JUL 27 2016

CONSERVATION DIVISION  
WICHITA, KS

7-27-16