

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-02323-00-00  
Spot: E2E2W2NW Sec/Twnshp/Rge: 26-11S-19W  
1320 feet from N Section Line, 3970 feet from E Section Line  
Lease Name: VINE "A" Well #: 8  
County: ELLIS Total Vertical Depth: 3615 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3588		135 sx
PROD	5.5	3610		25 SX
SURF	8.625	160		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2016 1:50 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL OPERATIONS Phone: (785) 483-1683

Proposed Plugging Method: Ordered 100 sx 60/40 pozmix 4% gel cement w/200 # hulls, 4 bags of CC.  
07/12/2016- Ordered 250 sx 60/40 pozmix 4% gel cement w/600 # hulls and 10 bags CC.  
DV Tool at 1400' w/600 sx cement.  
03/10/2011- Squeezed at 1752' - 1813' w/550 sx cement.  
03/11/2011- Squeezed at 1752' - 1813' w/600 sx cement.  
Casing parted at 1721'. Removed tubing that was stuck in hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/12/2016 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Express Well Service ran in hole with tubing to 1715'. Quality rigged to tubing and pumped 40 sx 5% cc followed by 60 sx cement w/5% cc and 200 # hulls mixed in. Let cement set overnight.  
07/12/2016- Ran in hole to 1715'. Did not tag any cement. Pumped 80 sx 5% cc w/400 # hulls. Pulled tubing and let cement set one hour. Ran in hole to 600' and pumped 65 sx cement to circulate cement to surface. Pulled tubing and topped off 4 1/2" casing with 10 sx cement. Hole standing full. Visually checked 8 5/8" surface casing and was full of cement.


GPS: 39.07034 -099.39938

Remarks: QUALITY CEMENTING CO TICKET # 1988 AND 1989

Plugged through: TBG

District: 04

Received Signed  
KANSAS CORPORATION COMMISSION

  
(TECHNICIAN)

JUL 29 2016  
CJA

JUL 14 2016

JUL 27 2016  
CONSERVATION DIVISION  
WICHITA, KS