

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23618-00-00
Spot: E2NE Sec/Twnshp/Rge: 4-34S-3E
4020 feet from S Section Line, 660 feet from E Section Line
Lease Name: ABRAMS Well #: 1
County: COWLEY Total Vertical Depth: 2915 feet

Operator License No.: 32599
Op Name: H.I.T. RESOURCES, INC.
Address: 25117 31ST ROAD
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		
PROD	4.5	2915		200 SX
SURF	8.75	150		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2016 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO. Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 1950', W/5 SXS. PERFORATE & CIRCUALTE 350'-0'.

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL
Date/Time Plugging Completed: 06/10/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 1960', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND.
TAGGED SAND & CEMENT @ 1920'. 6-8-2016, RIH ON WIRELINE PERFORATED
SQUEEZE HOLES (2 HOLES) @ 350'-351'. 6-10-2016, RIH W/TBG @ 360', ELITE
CEMENTING ESTABLISHED CIRCUALTION, MIXED & PUMPED 100 SXS 60/40
POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #2823.

Perfs:

Top	Bot	Thru	Comments
2000	2004		CSG

Remarks: LANDOWNER WAS ALLOWED TO PLUG WITHOUT OPERATOR LICENSE.

Plugged through: TBG

no
JUL 29 2016

District: 02

Signed Duane Krueger
(TECHNICIAN)

KCC WICHITA
Form CP-2/3

JUL 19 2016

RECEIVED

✓