

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-03314-00-00
Spot: NESENW Sec/Twnshp/Rge: 14-16S-12W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: THEISEN Well #: 2
County: BARTON Total Vertical Depth: 3357 feet

Operator License No.: 6296
Op Name: HOLT, IVAN LEROY DBA LEROY HOLT
Address: PO BOX 30503
EDMOND, OK 73003

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3357		
SURF	8.625	621		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE FUNK Company: QUALITY WELL SERVIC, INC. Phone: (785) 483-1724

Proposed Plugging Method: HAYS DISTRICT REGULATIONS.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 09/27/2004 12:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

On 9-22-2004 Quality Well Service, Inc. ripped casing @ 1250', 820', & 300'.
On 9-27-2004 Allied Cementing Co. invoice # 18902 pumped 250sx 60/40 poz-mix 10% gel w/400# hulls. 700# Max PSI, and Shut in @ 250#. Hooked up to backside and pumped 50 sx cement w/100# hulls 500# Max PSI, and Shut in @ 400#.

Perfs:

Top	Bot	Thru	Comments
3260	3266		
3246	3248		
3196	3206		
3128	3132		
3040	3048		

Remarks: ALLIED INVOICE # 18902

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN) [Signature]

JUL 29 2016

JUN 28 2016

Received
KANSAS CORPORATION COMMISSION

JUL 08 2016

CONSERVATION DIVISION
WICHITA, KS