

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21756-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 24-12S-31W
1500 feet from N Section Line, 1350 feet from E Section Line
Lease Name: BONITA SPRINGS Well #: 3
County: GOVE Total Vertical Depth: 4613 feet

Operator License No.: 34055
Op Name: H & M PETROLEUM CORPORATION
Address: PO BOX 2487
COLORADO SPRINGS, CO 80901

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4608		165 SX
SURF	8.625	219		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2016 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MATTHEW J. MONDERO Company: H & M PETROLEUM CORPORATIO Phone: (785) 475-4299

Proposed Plugging Method: Ordered 355 sx 60/40 pozmix 4% gel cement w/300 # hulls.
PC: 2347' w/200 sx cement.
CIBP: 4120. Perfs below plug- 4128' - 4130' and 4093' - 4095'.
Perforations: 4078' - 4082'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2016 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4080' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 2387' and pumped 100 sx cement. Pulled tubing to 1388' and pumped 135 sx cement. Good circulation of cement. Pulled tubing out and topped off casing w/10 sx cement. Tied on to backside and squeezed with 60 sx cement.

GPS: 39.00023 -100.70805

Perfs:

Top	Bot	Thru	Comments
4493	4495		
4128	4130		
4078	4082		

Remarks: SWIFT CEMENT TICKET # 29538

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN) *MD*

JUL 29 2016 CM

JUN 23 2016

Received
KANSAS CORPORATION COMMISSION

JUL 08 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3