

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20823-00-01
Spot: NENENENE Sec/Twnshp/Rge: 8-19S-6W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: LIGHTHILL Well #: 1
County: RICE Total Vertical Depth: 3171 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3171		150 SX
SURF	8.625	237		200 SX
T1	2.375	3126		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2016 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-7589

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/14/2016 9:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. RUN TUBING TO 3160' AND PUMP 35 SX'S CEMENT. PULL TUBING OUT AND PERFORATE AT 900', 550', AND 290'. RUN TUBING BACK DOWN TO 900' AND PUMP 35 SX'S. PULL TUBING UP AND WAIT 1.25 HRS. RUN TUBING BACK DOWN AND ATTEMPT TO TAG CEMENT - DIDN'T APPEAR CEMENT WAS PRESENT. RUN TUBING BACK TO 900' AND PUMPED 35 SX'S. SHUT DOWN FOR DAY. CAME BACK ON 7-14-16 AND TAGGED CEMENT AT 260'. RUN TUBING IN TO 250' AND PUMPED 100 SX'S. CEMENT GETTING CEMENT CIRCULATION OUT OF BOTH CASINGS. PULL TUBING OUT AND TOP OFF. USED 205 SX'S TOTAL CEMENT ON JOB.

Perfs:

Top	Bot	Thru	Comments
3171	3222	CSG	
3030	3171	CSG	

Received
KANSAS CORPORATION COMMISSION
JUL 26 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENT C-44159.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JUL 26 2016
CONSERVATION DIVISION
WICHITA, KS

W
JUL 29 2016
Form CP-2/3

✓