

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-20701-00-00  
Spot: SWNW Sec/Twnshp/Rge: 12-20S-8W  
3317 feet from S Section Line, 4624 feet from E Section Line  
Lease Name: WHARTON Well #: 1  
County: RICE Total Vertical Depth: 1378 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1378		75 SX
SURF	7	209		85 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/12/2016 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 562-7589

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/12/2016 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, COULDN'T GET THRU AT 800'. HAD TO PUT BIT ON AND DRILL DOWN TO 1165'. PERFORATE AT 1050', 650', AND 260'. RUN TUBING TO 1160' AND PUMP 50 SX'S COMMON CEMENT. PULL TUBING OUT, LET SET FOR 1.5 HR'S. TAG CEMENT AT 600'. PUMPED 110 SX'S AND GOT CEMENT CIRCULATION OUT OF BOTH CASINGS. PULLED TUBING AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
1152	1175		CSG

Received  
KANSAS CORPORATION COMMISSION  
**JUL 26 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: LOG TECH OF KS. #8738. COPELAND TICKET # C-44156. COMPLIANCE DENIED TA.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

**JUL 26 2016**

CONSERVATION DIVISION  
WICHITA, KS

no  
**JUL 29 2016**

Form CP-2/3

✓