

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23866-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 13-6S-24W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: WORKMAN TRUST Well #: 13-1
County: GRAHAM Total Vertical Depth: 3950 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3948		150 sx cement
SURF	8.625	280		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2016 9:45 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: BOB PLANTE Company: H & C OIL OPERATING Phone: (785) 434-7434

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls and 10 sx gel.
CIBP: 3860'. Port Collar at 2151' w/300 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2016 10:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement w/200 # hulls, followed by 10 sx gel, followed by 200 sx cement. Shut in pressure 400 psi. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.53553 -099.94580

Perfs:

Top	Bot	Thru	Comments
3832	3837		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1986

Plugged through: CSG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN) *no* CM

JUL 20 2016

JUL 27 2016 *72716*

JUL 29 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3