

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-06893-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 18-14S-14W  
2318 feet from S Section Line, 337 feet from E Section Line  
Lease Name: CARROLL F Well #: 4  
County: RUSSELL Total Vertical Depth: 3247 feet

Operator License No.: <u>3553</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>CITATION OIL &amp; GAS CORP.</u>	PROD	7	3043		150 SX
Address: <u>14077 CUTTEN RD PO BOX 690688</u> <u>HOUSTON, TX 77269</u>	SURF	10	612		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2016 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: LIANA RAMIREZ Company: CITATION OIL & GAS CORP, DBA Phone: (281) 891-1590

Proposed Plugging Method: Ordered 650 sx 60/40 pozmix 4% gel cement w/1220 # hulls.  
Squeezed holes at 900' w/100 sx cement, 15' - 20' w/100 sx cement and 2133' w/100 sx cement.  
No Perforations - Holes from 735' - 2521'.  
Perforations: 2797' - 2984'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/23/2016 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Express Well Service ran in hole with tubing to 2750'. Allied rigged to tubing and pumped 100 sx cement w/300 # hulls mixed in. Pulled tubing to 2135' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1520' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 900' and pumped 135 sx cement w/200 # hulls to circulate cement up 7" casing. Pulled tubing. Rigged to 7" casing and pumped 75 sx cement to circulate cement up 10" casing. Shut in pressure on 10" and 7" casing 100 psi. Had a 200 # valve on 7" casing.


GPS: 38.83190 -098.91165

Remarks: ALLIED CEMENTING CO. TICKET # 68032

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JUL 08 2016

CONSERVATION DIVISION  
WICHITA, KS

no CM  
JUL 29 2016 Form CP-2/3

JUN 24 2016