

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-03239-00-01
Spot: W2SWNESW Sec/Twnshp/Rge: 10-10S-25W
1617 feet from S Section Line, 3754 feet from E Section Line
Lease Name: ELRICK UNIT Well #: 7-2
County: GRAHAM Total Vertical Depth: 4012 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4012		100 SX
SURF	8.625	186		115 SX

Well Type: EOR UIC Docket No: E14576.17 Date/Time to Plug: 07/20/2016 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS, LLC
Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS CORP. DBA Phone: (785) 798-5637

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations: 3770' - 3777', 3788' - 3791', 3812' - 3820', 3827' - 3833', 3856' - 3862'.
CIBP:3908'. Perforations below plug: 3921' - 3924', 3968' - 3969', 3985' - 3991'.
DV Tool at 2161'.
2 7/8" tubing cemented in hole to 3674'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2016 9:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report: Perfs:


Tied to tubing and pumped 80 sx cement w/100 # hulls. Shut in pressure 500 psi. Tied to backside and squeezed with 2 sx cement. Shut in pressure 200 psi.
GPS: 39.19436 -100.10221

Remarks: ALLIED CEMENT TICKET #68084

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUL 27 2016

CONSERVATION DIVISION
WICHITA, KS

JUL 29 2016
CC UIC Form CP-2/3

JUL 20 2016

727-16