

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21751-00-00  
Spot: NESESW Sec/Twnshp/Rge: 34-18S-28W  
1008 feet from S Section Line, 2953 feet from E Section Line  
Lease Name: HERNDON Well #: 1  
County: LANE Total Vertical Depth: 4650 feet

| Operator License No.: <u>30104</u>    | String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|---------------------------------------|--------|-------|------------|-------------|-----------------|
| Op Name: <u>CAMBRON, PAUL L.</u>      | DVT    |       | 2114       |             | WITH 245 SX CMT |
| Address: <u>118 N PENN PO BOX 384</u> | PROD   | 5.5   | 4410       | 0           | WITH 95 SX CMT  |
| <u>NESS CITY, KS 67560</u>            | SURF   | 8.625 | 267        |             | WITH 180 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2016 9:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Revd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: PUMP BOTTOM 35 SX CMT WITH 150# HULLS. PLUG AT 2150' CIRCULATE TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: WADE KLAUS Witness Type: NONE  
Date/Time Plugging Completed: 06/23/2016 12:10 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

PUMP 35 SX CMT & 150# HULLS TA 4300'. RUN TBG TO 2150' & PUMPED 190 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 350#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4172 | 4175 |      |          |

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed [Signature]

RECEIVED  
JUN 27 2016  
KCC DODGE CITY [Signature]

JA (TECHNICIAN)

[Signature]  
JUN 29 2016 Form CP-2/3