

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-30400-00-01  
Spot: SENWSE Sec/Twnshp/Rge: 26-33S-14W  
1650 feet from S Section Line, 1640 feet from E Section Line  
Lease Name: ELLIS Well #: 1  
County: BARBER Total Vertical Depth: 4880 feet

Operator License No.: 34941  
Op Name: BLESSED OPERATING LLC  
Address: 302 W. CENTRAL AVE.  
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4750		WITH 2 SX CMT
PROD	4.5	4877	1880	WITH 100 SX CMT
SURF	8.625	1280		WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2016 12:00 PM  
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC  
Proposal Revd. from: KENT ROBERTS Company: AMERICAN WELL SERVICE LLC Phone: (620) 672-5625

Proposed Plugging Method: CIBP @ 4750' WITH 2 SX CMT. PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 25 SX CMT TO SURFACE.

Plugging Proposal Received By: KEN SCOFIELD WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/21/2016 1:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4750' WITH 2 SX CMT. 1ST PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 50' WITH 30 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Perfs:

Top	Bot	Thru	Comments
4800	4821		MISSISSIPPIAN

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
JUL 22 2016  
KCC DODGE CITY

[Signature]  
JUL 29 2016 Form CP-2/3