

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-00218-00-00
Spot: SWSE Sec/Twnshp/Rge: 36-33S-31W
659 feet from S Section Line, 1910 feet from E Section Line
Lease Name: CARTER Well #: 2-36 (2)
County: SEWARD Total Vertical Depth: 5967 feet

Operator License No.: 34089
Op Name: AGRICULTURAL ENERGY SERVICES
Address: PO BOX 31865
EDMOND, OK 73003

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4278		WITH 2 SX CMT
PROD 7		5967	1640	WITH 200 SX CMT
SURF	9.625	1565		WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2016 1:00 PM
Plug Co. License No.: 32721 Plug Co. Name: ELDREDGE WELL SERVICE LLC
Proposal Revd. from: MIKE BRADY Company: AGRICULTURAL ENERGY SERVIC Phone: (405) 208-2096

Proposed Plugging Method: SET CIBP @ 5760' WITH 2 SX CMT. PLUG AT 1620' WITH 60 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2016 11:30 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 4278' WITH 2 SX CMT. STACKED OUT DUE TO CEDAR HILL SAND FILLING CASING. CUT CASING AT 1640'. 1ST PLUG AT 1595' WITH 60 SX CMT. GOOD CIRCULATION. POOH. SHUT DOWN. 7/20/16: TAG TOC @ 1455'. 2ND PLUG AT 585' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5804	5838		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed [Signature] (TECHNICIAN) [Signature]

RECEIVED
JUL 22 2016
KCC DODGE CITY

JUL 29 2016
Form CP-2/3