

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-22156-00-01  
Spot: SENWSE Sec/Twnshp/Rge: 9-6S-22W  
1381 feet from S Section Line, 1481 feet from E Section Line  
Lease Name: MARY RUSH Well #: 9-9-3  
County: GRAHAM Total Vertical Depth: 3963 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 300 W DOUGLAS AVE, STE 410  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3958		200sx
SURF	8.625	302		225 SX

Well Type: EOR UIC Docket No: E26139.1 Date/Time to Plug: 07/01/2016 8:00 AM  
Plug Co. License No.: 34737 Plug Co. Name: UNITED WELL SERVICE, LLC  
Proposal Revd. from: PRESTON DREILING Company: ANDERSON ENERGY Phone: (316) 263-1006

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
DV Tool at 1947' w/450 sx cement. Did not circulate.  
Top of cement at 1560'. Ran 1" to 300' and pumped 50 sx cement to circulate cement to surface.  
Perforations: 3551' - 3553', 3703' - 3705'.  
Shot perforations at 1450' and 400'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/01/2016 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3520' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 2870' and pumped 100 sx cement. Pulled tubing to 1480' and pumped 115 sx cement. Good circulation of cement. Tied on to casing and squeezed with 15 sx cement. Shut in pressure 500 psi. Backside has cement to surface.

GPS: 39.54296 -099.77408

Perfs:

Top	Bot	Thru	Comments
3703	3705		
3551	3553		

Remarks: QUALITY CEMENT TICKET # 1976

Plugged through: TBG

District: 04

Received  
KANSAS CORPORATION COMMISSION

Signed



(TECHNICIAN)

CM

JUL 27 2016

CONSERVATION DIVISION  
WICHITA, KS

JUL 29 2016  
CC UIC Form CP-2/3

JUL 06 2016