

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19979-00-00

Spot: SESWNWNE

Sec/Twnshp/Rge: 14-24S-12E

3991 feet from S Section Line, 2083 feet from E Section Line

Lease Name: WAYHAM

Well #: W 1

County: GREENWOOD

Total Vertical Depth: 1848 feet

Operator License No.: 5394

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1787		500 SX
SURF	8.625	245		150 SX

Well Type: SWD

UIC Docket No: E07558.1

Date/Time to Plug: 06/20/2016 11:00 AM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DWAIN STOUT

Company:

Phone: (316) 640-9072

Proposed
Plugging
Method:

Dump 50 ft. of sand on bottom. Pump 10 sax of cement on top of sand. Pump mud to 250 ft. Cement from 250 ft. to surface. Run 250 ft. 1" tubing between surface and production strings and cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/23/2016 12:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

dumped sand for bottom bridge @187 to 1550', pumped 10 sxs cement @ 1550', pumped 10 sxs cement @ 700', pulled tubing to 310' pumped 20 sxs cement to surface, gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
JUL 18 2016
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed

Mike D. [Signature]
(TECHNICIAN)

KCC WICHITA

JUL 21 2016

RECEIVED

JUL 29 2016
cc UIC Form CP-2/3

