

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19989-00-00

Spot: S2N2N2N2

Sec/Twnshp/Rge: 14-24S-12E

4730 feet from S Section Line, 2640 feet from E Section Line

Lease Name: SULLIVAN

Well #: W 15

County: GREENWOOD

Total Vertical Depth: 1821 feet

Operator License No.: 5394

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
PROD	4.5	1756		100 SX
SURF	8.625	131		100 SX

Well Type: EOR

UIC Docket No: E07558.19

Date/Time to Plug: 06/02/2016 12:00 PM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DWAIN STOUT

Company:

Phone: (316) 640-9072

Proposed
Plugging
Method:

Dump 50 ft. of sand on bottom. Pump 10 sacks cement on top of sand. Fill up with drilling mud to 700 ft. Shoot at 700 ft. Fill up with mud to 150 ft. Cement from 150 ft. to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/09/2016 3:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

dump sand from 1821' to 1700' for bottom bridge, pumped 10 sxs cement @ 1700' pulled casing to 718' pulled casing to 225' pumped 85 sxs cement to surface. gel spacers between cement plugs.

RECEIVED
KCC DIST #3
JUL 18 2016
CHANUTE, KS

mt

Remarks:

Plugged through: CSG

District: 03

Signed

Mike Deffen

(TECHNICIAN)

MD
JUL 29 2016
CC UIC

KCC WICHITA

JUL 21 2016

RECEIVED

Form CP-2/3

R.R.A., INC.510 Hardage Center
Wichita, Kansas 67202

Pho: 262-3411

FIELD REPORT

DATE 6-9-16

R.R.A.				WELL RECORD									
(Company) 100 S Main STE 510				PULLED					RUN				
(Address) 100 S Main STE 510				(Length) (Size)					Strainer Gas Anchor				
(Lease) Sullivan (Well No.) W-15				(Size) (Br'd) (No Cups)					Sta. Valve				
Greenwood				(No Cups) (No)					Pump				
				(Size)									
				(Brand)									
Unit No. Sec 14 - 24 1/2 - 12 E				Number Size Length					Number Size Length				
Unit Operator													
Floorman													
Floorman													
Other													
Total Unit Charge													
API 15-073-19989-00-00													
TD. 1321'													
4 1/2 @ 1756'													
REMARKS: Surface 8 5/8 131													
Sand Back to 1700'				Jct. Lgth. Size Thd.					Jct. Lgth. Size Thd.				
10 sk cmt 1700' to 1590'													
Gell hole to 1590' to 700'													
Cornish shot 4 1/2 off @ 718' Pulled													
Pumped 20 sk cmt @ 700 to 650													
Gell 750' to 225'													
85 sk cmt 225' to surface													
Comp.													
6-9-16													
				R.R.A. Tools					RECEIVED KCC DIST #3 JUL 13 2016 CHANUTE, KS				

By

KCC WICHITA

JUL 21 2016

RECEIVED

JUL 29 2016