

1 090129

10-9
API NUMBER 15-093-21,187-0000

76
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW NE, SEC. 21, T 24 S, R 36 W/EX

3300 feet from S section line

1980 feet from E section line

Lease Name Bret Well # 1-21

County Kearny 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1583

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: BEREXCO Inc.

Name & Address 970 Fourth Financial Ctr.

Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BEREDCO Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 12 a.m. Day: 9 Month: 10 Year: 1991

Plugging proposal received from Kenny

(company name) BEREDCO Inc. (phone) 316-265-2856

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1407-1570'

1st plug at 3300' with 100 sx cement, 2nd plug at 1600' with 50 sx cement,

3rd at 700' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 a.m. Day: 9 Month: 10 Year: 1991

ACTUAL PLUGGING REPORT 1st plug at 3250' with 100 sx cement,

2nd plug at 1600' with 50 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE 10-29-91

INV. NO. 33540

Signed _____ (TECHNICIAN)

10-15-91
RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1991
CONSERVATION DIVISION